

#### Part 1 - GENERAL

## 1.01 SUMMARY

A. Furnish Expansion Joint System in accordance with the drawings and general provisions of the Contract.

## 1.02 WORK INCLUDED

- A. Furnish complete Prospec Specialties Expansion Joint Systems.
- 1. Interior floor expansion joint systems.
- 2. Exterior floor expansion joint systems.

#### 1.03 RELATED WORK

- A. Related work which is specified elsewhere.
- 1. Cast-in-Place Concrete: Section 03300.
- 2. Structural Steel: Section 05120.

### 1.04 REFERENCES

- A. Publications listed herein are part of this specification to the extent referenced. The criteria established in the specifications shall take precedence over the standards referenced herein. (An example of a reference standard is given below.)
- 1. American Society for Testing and Materials (ASTM):
- a. ASTM B 221, Standard Specifications for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Shapes, and Tubes.

#### 1.05 DEFINITIONS

A. Define industry and product terms as necessary.

## 1.06 SYSTEM DESCRIPTION

- A. Joint systems shall permit limited movement of joint without disengagement.
- 1. Specify x-axis joint movement (horizontal).
- 2. Specify y-axis joint movement (vertical).
- 3. Specify z-axis joint movement (lateral).
- B. Fire Rated Assemblies shall have been tested by Underwriter's Laboratories, in accordance with UL 2079 including hose stream test at full rated period. Underwriter's Laboratories shall classify assemblies. Fire rating shall be 2 hours or not less than the fire rating of adjacent construction.

## 1.07 QUALITY ASSURANCE

- A. Manufacturer: Furnish Expansion Joint Cover assemblies from single manufacturer.
- B. Installer: Firm with not less than three (3) years of successful experience in the installation of systems similar to those required by this project and acceptable to the manufacturer of the system.

# 1.08 SUBMITTALS

- A. Manufacturer's specifications, technical data, installation instructions, and detail drawings for each system.
- B. Certificates or other documentation confirming UL approved compliance with fire resistance rating of fire barrier assemblies.
- C. Sample of specified systems where required.



#### 1.09 DELIVERY AND STORAGE

- A. Provide temporary protective covers on [anodized aluminum] [stainless steel] finished surfaces.
- B. Deliver joint systems to jobsite in new, clean, unopened cartons or crates of sufficient size and strength to protect materials during transit.
- C. Store components in original containers in a clean, dry location.

#### 1.10 SEQUENCING

- A. Submittals shall be completed and submitted within a reasonable amount of time after award of subcontract.
- B. Subcontract for the work of this section shall be planned to allow sufficient time for manufacturer's production and delivery scheduling.

#### 1.11 WARRANTY

A. Standard Prospec Specialist Inc. limited warranty against material and manufacturing defects for a period of not less than three (3) years when installed in accordance with manufacturer's recommendations.

### PART 2 - PRODUCTS

#### 2.01 MANUFACTURER

A. Prospec Specialties Inc.

26-5250 Satellite Drive, Mississauga,

Ontario L4W 5G5, Canada

- B. Substitutions: Not permitted.
- C. Request for substitutions will be considered in accordance with provisions of section 01600.

#### 2.02 MATERIALS

- A. Extruded EPDM/Santoprene Seal: Prospec Specialties KC Series
- B. Sikadur-31 CF Slow Adhesive (by others)
- C. Pro-Mortar (Elastomeric Concrete Header)

#### 2.03 FABRICATION

- A. Field assembled seals provided in longest length available with adhesive and accessories.
- B. Fabricate special transitions and corner fittings as required. Miter and weld elastomeric seal as applicable.

### PART 3 - EXECUTION

3.01 A. Verify that structural gap and block-out dimensions are in conformance with manufacturer's submittal data.

## 3.02 INSTALLATION

- A. Joint Systems: Install in accordance with manufacturer's instructions. Align work plumb, level and flush with adjacent surfaces. Rigidly anchor to substrate. Allowances should be made where actual structural gap at time of installation varies from nominal design gap.
- B. Fire Rated Assemblies: Where required, install as per manufacturer's instructions.

# 3.03 PROTECTION AND CLEANING

- A. Protect installation from damage by work of others.
- B. At completion of the installation, clean exposed surfaces with non-solvent cleaner.